

Nordonia Hills City School District

9370 Olde 8 Rd.
Northfield Ohio 44067



Summer Roofing Projects
Middle School Roof Replacement
73 Leonard Ave.
Northfield Ohio 44607

4.25.2022

Addendum #2, Clarification Items:

1. **Are liquid damages to be included in the bonding?** No. However, proper documentation must be provided (material shortages, weather, supply chain disruptions, etc.) outlining the reason for a delay.
2. **Insulation:** The Nordonia Hills School District is providing 232 squares of flat 2.2" polyisocyanurate. The contractor is responsible for any overages, tapered saddles/tapered crickets, and sumped drains.
3. Infill between the ribs with insulation and/or coverboard. A cover board must be used and the top layer. Install a fully adhered non-fleece back KEE, extend down the vertical wall, and heat weld to the PVC coated counter flashing.



Nordonia Hills City Schools

9370 Olde 8 Rd.
Northfield Ohio 44067

Summer Roofing Projects
Middle School Roof Replacement
73 Leonard Ave.
Northfield Ohio 44607



04.18.2022

Addendum #2:

As per the conversation in the bid meeting, the following topics below were addressed, changes and or further clarification need made.

1. Mandatory bid meeting; all in attendance signed in. Sign in sheet on record.
2. Bids are due on the 29th following the instruction in the bid packet.
3. **Are liquid damages to be included in the bonding?**
4. Insulation is being procured by Nordonia Hills City Schools.
 - a. **Contractors are to not have insulation included in their bid?**
 - b. **Garland is coordinating insulation delivery and eta with the school district.**
 - c. **Plates and fasteners to be purchased by the contractor.**
5. Static wall to have the existing coping cap removed and new metal coping installed.



6. **Curb to have tapered insulation on top of the unit?**
 - a. **What is the system and is there a detail?**



7. Gas lines near the unit/curb to be moved by others. Not responsibility of the contractor.

